

University of Lucknow

Notice Inviting Tenders (Short Term)

Sealed tenders are invited from registered contractors of Works Department for **Construction of N.S.S Building (Ground Floor + First Floor) Near Department of Social Work** as per detail attached as Annexure-1.

The terms and conditions along-with format of technical and financial bid respectively (Tender documents set) can be downloaded from www.lkouniv.ac.in displayed as Annexure A, B and C respectively along with this notice.

The tender bids (separate technical and financial bids double sealed in one envelope) addressed to the Executive Engineer, University of Lucknow are required to be placed in the tender box at Proctor Office, University of Lucknow, Lucknow-226007 by the Last date of June 26, 2019 (2.00 PM). The bids shall be opened at 3.00 PM in the Office of the Proctor on the same day.

**Executive Engineer
University of Lucknow**

Works Department, University of Lucknow

Description of Work:- Construction of N.S.S Building (Ground Floor + First Floor) Near Department of Social Work.

SI.No.	Particulars of Work	Qty.	Unit
1-251/ PWD	The earthwork in excavation in trenches for foundation, pipes and cable etc in ordinary soil (loam clay & sand) including lift of 15m & lead of 30m and dressing of sides and ramming of bottom and disposal of surplus excavated earth as directed.	58.11	Cum.
2- 2.25/ DSR	Filling of available excavated earth in trenches etc. in layers not exceeding 20cms in depth, consolidating each deposited layer by ramming and watering including lead up 50m. and lift up to 1.5m..	58.11	Cum
3-MR	Filing of catered earth in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering including lead up to 50m and lift up to 1.5m	15.00	Cum.
4- 2.35. 1/CPWD , DSR	Providing and injecting chemical emulsion for preconstruction Anti termite treatment and creating a chemical barrier under and creating a chemical barrier under and around the column pits wall trenches using chlopyriphos emulsion concentration of 20% solution in foundation & below flooring.	182.00	Sqm
5. 281/ PWD	Providing and laying in cement concrete 1.5:10 (1 cement : 5 fine sand 10 graded brick aggregate 40mm nominal size) and curing complete including cost of formwork foundation and floors.	18.66	Sqm
6-287/ PWD SOR 2015- 2016	R.C.C. work with cement approved coarse sand and 2cm (3/4") gauge approved stone ballast in proportion 1:1:5:3 (1 cement : 45 aggregate) including supply of all materials, labour and tools & plants etc required for proper completion of work. Strength of concrete should not less than M.200 for foundation and plinth beam.	14.03	Cum.
7- DSR	Fixing and renovating of shuttering for R.C.C. work in foundation & plinth beam including applying shuttering oil.	21.48	Sqm
8- 303 PWD	Class-150 brick work in 1:6 cement and fine sand of 1.25 fineness modulus mortar in foundation and plinth including supply of all materials laobur and tools & plants etc. required for proper completion of work.	26.00	Cum.
B	Super Structure Work		
1-289 PWD	R.C.C. work with cement approved coarse sand and 2cm (3/4") gauge approved stone ballast in proportion 1:1:5:3 (1cement 4, 5 aggregate) including supply of all materials, labour and tools & plants etc. required for proper completion of work strength of concrete should not less than M. 200 for columns.		
2- 284 PWD	Same as itme NO. B1 for (A) Beams (B) Slabs	11.63	Cum.
	Same as item No. B1 for lintels, sunshades canopies etc.		
	Fixing and removing of shuttering for R.C.C work in Column including applying shuttering oil.	13.61	Cum.

3- 283 PWD	Same as item No. B5 but for slab and beams.	31.35	Cum.
4- 5.9.6 DSR	Same as item no. B5 but for Lintels, sunshades Canopies etc.	1.05	Cum.
5- 5,9,3 DSR	Tor steel work in plain work such as reinforced concrete or reinforced brick work to required shape as necessary including bending binding for proper completion of the work in super structure.	59.06	Sqm.
6- 5.9.5 DSR	Class-150 brick work in 1:6 cement and fine, sand of 1.25 fineness modules mortar above plinth including supply of all materials, labour and tools & plants etc. required for proper completion of work.	342.58	Sqm.
7- 504 PWD	Class-150 brick work in 1:4 cement and coarse sand of 2.25 fineness modules mortar above including supply of all materials, labour and tools & plants etc. required for proper completion of work.	15.44	Sqm.
8- 303, PWD	Providing and laying damp proofing course 25mm thick cement concrete 1:2:4 (Cement 1:2 coarse sand 4 graded stone aggregate 10mm. nominal size) and curing complete. Painting on D.P.C. with two coats of air blown bitumen 85/25 @ 1.7 Kg/ Sqm. Aprox including cost of fuel if any.	33.77	Qtl.
9-310(a) PWD	10mm thick plastering on calling in 1:4 complete in all respect with proper curing.	64.51	Cum.
10- 361 PWD	50mm thick cement concrete flooring in 1:2:4 lald and floating coat of neat cement including supplying and fixing of 35x4 mm glass strip complete including rubbing to smooth finish with granite polish.	7.25	Cum.
11-387 PWD	20mm thick plastering in 1:4 on skirting with floating coat of neat cement.	10.35	Sqm.
12-604 PWD 2015	Supplying & fixing of 6mm thick china white/grey glazed tile on flooring complete kazaria / Nitco or as approved by client.	903.14	Sqm.
13-597 PWD	Supplying & fixing of 6mm thick china white/ grey glazed tile on walls completes.	65.00	Sqm.
14- 11.36 DSR	Door/window frame including butt. hinges of 100x3mm. drilling holes for L-drope and pipes 15x12 mm. cleats for towel bolt and 40x6 mm hold fast 230 mm. long including concreting in below portion & fixing complete.	8.00	Sqm.
15- 11.38 DSR	Supply & fixing of window ventilator Mild steel grill and per design complete & as per direction of Engineer incharge..	40.80	Sqm.
16- 10.14.3. 2 DSR	Supplying and fixing of 32mm thick water proof factory made phenol formaldehyde bonded plywood door shutters as per specification including necessary fittings. Hinges at handles screws tower bolts. Etc. as per direction of Engineer incharge.	100.80	Sqm.
17- 503 PWD	Supplying and dinging of flush door shutter stainless steel fittings Handles, towel bolt sliding bolts door stopper, silencer etc fittings complete.	60.00	Mtr.
18-9.21. 2 DSR	Supplying and fixing 4 mm thick glass panes in windows complete	1115.0 0	Kg.
19-DSR	Inside oil bound distemper on undecorated wall surfaces two or more coats including preparation of walls smooth & even.	15.15	Sqm.
20- MR	Providing and applying 3 coats of enamel paint on Wooden/ steel surfaces including priming coat complete wooden surface & Steel Surface .	6.00	Nos.

21- PWD 649+ 650	Making grooves 10 to 12mm wide 8 mm deep in plaster.	13.50	Sqm.
22- 641+ 642 PWD	Making drip courses on sunshade complete.	690.00	Sqm.
23- MR	Making kota stone flooring as per drawing with granite polish finish.	108.00	Sqm.
24- MR	P/L 100 mm dia. Rain water pipe 4 kg/M of standard make with drain outlet khurrah, clamps & brackets complete.	310.00	R/M
25- 11.26 DSR	Making water proofing brick coba treatment. A) Making top of roof with 2 take coat of CICO or any equivalent water proofing coat. B) Making necessary slope in 1:3:6 & 1:2:4 cement concrete in drain out the water. C) Providing brick bat Koba treatment in 1:3:6 with necessary slope and using glass strips filling and spreading 2 coats or tack coat of CICO water proofing compound on glass trip so no water seeps into.	132.00	Sqm.
26- 14.41.2 DSR	600x600 mm. vitrified tile complete in Johnson / Kajaria as per approved of director.	196.00	Sqm.
27-22.7 DSR	P/A Birla puttee two coat to make smooth and even surface wall and ceiling.	1080.00	Sqm,
28- 11.41.2 DSR	Apex painting on exterior Surface two coats.	390.00	Sqm.
29-13.81 DSR	P/F stainless steel railing.	175.00	Kg.
30-13.45 DSR	P/F Aluminium window Bombay sliding.	27.71	Sqm.
31- 10.28 DSR	Extra for scaffolding.	360.00	Sqm.

**Executive Engineer
University of Lucknow.**

Works Department, University of Lucknow

Terms and Conditions: Construction of N.S.S Building (Ground Floor + First Floor) Near Department of Social Work.

1. The rates quoted should be net exclusive of Goods and Service Tax.
2. No payment shall be paid for the cartage. (Rate should be F.O.R. site).
3. The work should be completed within the stipulated time given from the date of order as mentioned in work order.
4. Quantities are liable to vary.
5. Payment shall be made on the basis of actual work executed.
6. An earnest money of Rs. 60000.00 in the form of Bank Draft issued by a Nationalized, Bank in favour of “Finance Officer, University of Lucknow” payable at Lucknow should accompany the tender form which shall be refunded to those whose tenders are not accepted.
7. EMD will be converted into security money for the tenderer whose bid is accepted.
8. Only those tenders shall be accepted which give the offer for entire work (tender for part work will not be accepted).
9. The Vice Chancellor, University of Lucknow will have absolute right to reject the tender without assigning any reason.
10. Demand Draft of Rs. 1000.00 being cost of tender form has to be attached with Tender form in favour of “Finance Officer, University of Lucknow” payable at Lucknow, which is not refundable in any case.
11. Tender form will be deposited in the office of the Proctor, University of Lucknow, Last date of tender form submission is 26.06.2019 upto 2:00 PM. The tender will be opened on 26.06.2019 at 3:00 PM. In the office of The Proctor, University of Lucknow.
12. The bidder firm shall possess experience of similar work and attach proof in support.
13. Registration with Government departments such as PWD is preferable.
14. PAN & GST Certificate is essential, attested copies of same are to be attached.
15. Authorized signatory has kept all the original documents at the time of opening of tender.
16. All disputes are subjects to Lucknow Jurisdiction.
I/We have read and understand the above conditions and agree to abide by them.

Authorized Signatory & Seal of the Tenderer

University of Lucknow

Description of Work: Construction of N.S.S Building (Ground Floor + First Floor) Near Department of Social Work.

Format/ Check list of Technical Bid

S.No.	Description	Yes	No
1.	Name of the firm		
2.	Address Contact No.		
3.	Attach : Firm registration/ Partnership Registration Company Certificate (Attached Photocopy)		
4.	G.S.T. Registration (Attach Photocopy)		
5.	Permanent Account Number. Issued by Income Tax Department. (Attached Photocopy)		
6.	Furnish Demand draft of Rs. 1000.00 in favour of Finance Officer, University of Lucknow towards cost of application (Non-refundable).		
7.	Furnish DD of Rs. 60000.00 in favour of Finance Officer, University of Lucknow towards EMD DD No. Issuing Bank Date of Issue		

Authorized Signatory Seal of the Tenderer

Annexure – C

Works Department, University of Lucknow

Name of Work : Construction of N.S.S Building (Ground Floor + First Floor) Near Department of Social Work.

Format of Financial Bid

I/we here by tender the following rates for different items as under.

SI.No.	Particulars of work	Qty.	Unit	Rate per Unit (Rs.)	Amount (Rupees)
1-251/ PWD	The earthwork in excavation in trenches for foundation, pipes and cable etc in ordinary soil (loam clay & sand) including lift of 15m & lead of 30m and dressing of sides and ramming of bottom and disposal of surplus excavated earth as directed.	58.11	Cum.		
2- 2.25/ DSR	Filling of available excavated earth in trenches etc. in layers not exceeding 20cms in depth, consolidating each deposited layer by ramming and watering including lead up to 50m. and lift up to 1.5m..	58.11	Cum		
3-MR	Filing of catered earth in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering including lead up to 50m and lift up to 1.5m	15.00	Cum.		
4- 2.35. 1/CPWD, DSR	Providing and injecting chemical emulsion for preconstruction Anti termite treatment and creating a chemical barrier under and around the column pits wall trenches using chlopyriphos emulsion concentration of 20% solution in foundation & below flooring.	182.00	Sqm		
5. 281/ PWD	Providing and laying in cement concrete 1.5:10 (1 cement : 5 fine sand 10 graded brick aggregate 40mm nominal size) and curing complete including cost of formwork foundation and floors.	18.66	Sqm		
6-287/ PWD SOR 2015- 2016	R.C.C. work with cement approved coarse sand and 2cm (3/4") gauge approved stone ballast in proportion 1:1:5:3 (1 cement : 45 aggregate) including supply of all materials, labour and tools & plants etc required for proper completion of work. Strength of concrete should not less than M.200 for foundation and plinth beam.	14.03	Cum.		
7- DSR	Fixing and renovating of shuttering for R.C.C. work in foundation & plinth beam including applying shuttering oil.	21.48	Sqm		
8- 303 PWD	Class-150 brick work in 1:6 cement and fine sand of 1.25 fineness modulus mortar in foundation and plinth including supply of all materials laobur and tools & plants etc. required for proper completion of work.	26.00	Cum.		

B	Super Structure Work				
1-289 PWD	R.C.C. work with cement approved coarse sand and 2cm (3/4") gauge approved stone ballast in proportion 1:1:5:3 (1cement 4, 5 aggregate) including supply of all materials, labour and tools & plants etc. required for proper completion of work strength of concrete should not less than M. 200 for columns.				
2- 284 PWD	Same as itme NO. B1 for (A) Beams (B) Slabs	11.63	Cum.		
	Same as item No. B1 for lintels, sunshades canopies etc.				
	Fixing and removing of shuttering for R.C.C work in Column including applying shuttering oil.	13.61	Cum.		
3- 283 PWD	Same as item No. B5 but for slab and beams.	31.35	Cum.		
4- 5.9.6 DSR	Same as item no. B5 but for Lintels, sunshades Canopies etc.	1.05	Cum.		
5- 5,9,3 DSR	Tor steel work in plain work such as reinforced concrete or reinforced brick work to required shape as necessary including bending binding for proper completion of the work in super structure.	59.06	Sqm.		
6- 5.9.5 DSR	Class-150 brick work in 1:6 cement and fine, sand of 1.25 fineness modules mortar above plinth including supply of all materials, labour and tools & plants etc. required for proper completion of work.	342.58	Sqm.		
7- 504 PWD	Class-150 brick work in 1:4 cement and coarse sand of 2.25 fineness modules mortar above including supply of all materials, labour and tools & plants etc. required for proper completion of work.	15.44	Sqm.		
8- 303, PWD	Providing and laying damp proofing course 25mm thick cement concrete 1:2:4 (Cement 1:2 coarse sand 4 graded stone aggregate 10mm. nominal size) and curing complete. Painting on D.P.C. with two coats of air blown bitumen 85/25 @ 1.7 Kg/ Sqm. Aprox including cost of fuel if any.	33.77	Qtl.		
9-310(a) PWD	10mm thick plastering on calling in 1:4 complete in all respect with proper curing.	64.51	Cum.		
10- 361 PWD	50mm thick cement concrete flooring in 1:2:4 lald and floating coat of neat cement including supplying and fixing of 35x4 mm glass strip complete including rubbing to smooth finish with granite polish.	7.25	Cum.		
11-387 PWD	20mm thick plastering in 1:4 on skirting with floating coat of neat cement.	10.35	Sqm.		
12-604 PWD 2015	Supplying & fixing of 6mm thick china white/grey glazed tile on flooring complete kazaria / Nitco or as approved by client.	903.14	Sqm.		

13-597 PWD	Supplying & fixing of 6mm thick china white/ grey glazed tile on walls completes.	65.00	Sqm.		
14- 11.36 DSR	Door/window frame including butt. hinges of 100x3mm. drilling holes for L-drope and pipes 15x12 mm. cleats for towel bolt and 40x6 mm hold fast 230 mm. long including concreting in below portion & fixing complete.	8.00	Sqm.		
15- 11.38 DSR	Supply & fixing of window ventilator Mild steel grill and per design complete & as per direction of Engineer incharge..	40.80	Sqm.		
16- 10.14.3.2 DSR	Supplying and fixing of 32mm thick water proof factory made phenol formaldehyde bonded plywood door shutters as per specification including necessary fittings. Hinges at handles screws tower bolts. Etc. as per direction of Engineer incharge.	100.80	Sqm.		
17- 503 PWD	Supplying and dixing of flush door shutter stainless steel fittings Handles, towel bolt sliding bolts door stopper, silencer etc fittings complete.	60.00	Mtr.		
18- 9.21.2 DSR	Supplying and fixing 4 mm thick glass panes in windows complete	1115.00	Kg.		
19-DSR	Inside oil bound distemper on undecorated wall surfaces two or more coats including preparation of walls smooth & even.	15.15	Sqm.		
20- MR	Providing and applying 3 coats of enamel paint on Wooden/ steel surfaces including priming coat complete wooden surface & Steel Surface .	6.00	Nos.		
21- PWD 649+650	Making grooves 10 to 12mm wide 8 mm deep in plaster.	13.50	Sqm.		
22- 641+ 642 PWD	Making drip courses on sunshade complete.	690.00	Sqm.		
23- MR	Making kota stone flooring as per drawing with granite polish finish.	108.00	Sqm.		
24- MR	P/L 100 mm dia. Rain water pipe 4 kg/M of standard make with drain outlet khurrah, clamps & brackets complete.	310.00	R/M		
25- 11.26 DSR	Making water proofing brick coba treatment. a) Making top of roof with 2 take coal of CICO or any equivalent water proofing coaf. b) Making necessary slope in 1:3:6 & 1:2:4 cement concrete in drain out the water. c) Providing brick bat Koba treatment in 1:3:6 with necessary slope and using glass strips filling and spreading 2 coats or tack coat of CICO water proofing compound on glass trip so no water seeps into.	132.00	Sqm.		
26- 14.41.2 DSR	600x600 mm. vitrified tile complete in Johnson/Kajaria as per approved of director.	196.00	Sqm.		

27-22.7 DSR	P/A Birla puttee two coat to make smooth and even surface wall and ceiling.	1080.00	Sqm,		
28-11.41. 2 DSR	Apex painting on exterior Surface two coats.	390.00	Sqm.		
29-13.81 DSR	P/F stainless steel railing.	175.00	Kg.		
30-13.45 DSR	P/F Aluminium window Bombay sliding.	27.71	Sqm.		
Total					
Good & Services Tax @.....					
Grand Total					

**Signature of Authorized Signatory
and Seal of the Tenders**