

## **University of Lucknow**

### **Notice Inviting Tenders (Short Term)**

Sealed tender are invited from registered contractors of Works Department for **Development of Parking near UCO Bank Building**, University of Lucknow as per details attached at Annexure-1.

The terms and conditions along-with formats of technical and financial bid respectively (Tender documents set) can be downloaded from [www.lkouniv.ac.in](http://www.lkouniv.ac.in) displayed as Annexure A, B and C respectively along with this notice.

The tender bids (separate technical and financial bids double sealed in one envelop) addressed to the Executive Engineer, University of Lucknow-226007 be submitted in the office of Proctor, University of Lucknow by the last date of 06.09.2019 upto 3.00 PM. The bids shall be opened at 4.00 PM in the office of The Proctor, University of Lucknow.

**Executive Engineer  
University of Lucknow**

**Annexure-I****Works Department, University of Lucknow****Description of work: Development of Parking near UCO Bank Building.**

<b>Sl. No.</b>	<b>Particulars of Work</b>	<b>Qty.</b>	<b>Unit</b>
1.	Dismantling of brick wall as per S.I. No. 692	76.00	m <sup>3</sup>
2.	Earth work in excavation as per S.I. No. 252.	69.30	m <sup>3</sup>
3.	Laying cement concrete as per S.I. No. 275.	17.33	m <sup>3</sup>
4.	Brick work in wall as per S.I. No. 305(b).	171.47	m <sup>3</sup>
5.	Plastering over wall as per S.I. No. 583	700.76	m <sup>2</sup>
6.	Plastering over wall as per S.I. No. 584.	175.00	m <sup>2</sup>
7.	Preparation of base with putty as per D.S.R. item No. 13.80	410.00	m <sup>2</sup>
8.	Painting with weather coat as per DSR. Item No. 13.47.1	412.00	m <sup>2</sup>
9.	Preparation and consolidation of subgrade as per DSR item no. 16.1 .	1260.00	m <sup>2</sup>
10.	Supply and stacking of stone screening 11.20mm nominal size and laying spreading and compacting stone aggregate as per DSR item no. 16.37+16.40.	210.00	m <sup>3</sup>
11.	Providing and laying 80mm thick zig-zag in interlocking tiles as per UPPWD rate. (Chapter 20)	1260.00	m <sup>2</sup>
12.	Providing and laying non-pressure NP-3 class RRC pipe as per DSR item no. 19.35.5 (1200mm dia RCC pipe).	8.00	Mt.
13.	Construction of brick masonry main hole as per DSR item No. 19.7.3.1 + 19.8.2.1 size 120x90cm x (2.90).	03	No.
14.	Providing and laying non-pressure NP-3 class as per DSR item no. 19.35.2 600mm dia RCC Pipe.	23.50	Rmt.
15.	Providing and laying cement concrete as per DSR Item No. 5.1.2.	34.800	m <sup>3</sup>
16.	Mild steel work in plane as per S.I. No. 504.	36.50	Qtl.
17.	Providing and laying drain water pipe of 110mm dia PVC pipe of 6.00 kg/cm <sup>2</sup> pressure.	66.00	Mt.
18.	Providing and laying drain water pipe line as per required in depth having 75mm dia 6.00 kg/cm <sup>2</sup> pressure.	66.00	Rmt.
19.	Fabrication of M.S. gate as per S.I. No. 503.	505.00	Kg
20.	Dismantling of cement concrete dumped in culvert by LMRC. a. Mason b. Labour	08 20	No. No.
21.	20mm plastering and finish with neat cement over concrete surface S.I. No. 597.	310.00	m <sup>2</sup>

**Executive Engineer  
University of Lucknow.**

**Works Department, University of Lucknow**

**Condition For: Development of Parking near UCO Bank Building.**

1. The rates quoted should be net exclusive of Goods and Service Tax.
2. No payment shall be paid for the cartage. Rate should be F.O.R. site).
3. The work should be completed within the stipulated time given from the date of order as mentioned in work order.
4. Quantities are liable to vary.
5. Payment shall be made on the basis of actual work executed.
6. An earnest money of Rs. 65000.00 in the form of Bank Draft issued by a Nationalized. Bank in favour of “Finance officer, University of Lucknow” payable at Lucknow should accompany the tender form which shall be refunded to those whose tenders are not accepted.
7. EMD will be converted into security money for the tenderer whose bid is accepted.
8. Only those tenders shall be accepted which give the offer for entire work (tenders for part work will not be accepted).
9. The Vice Chancellor, University of Lucknow will have absolute right to reject the tender without assigning any reason.
10. Demand Draft of Rs. 1180.00 including 18% GST being cost of tender form has to be attached with Tender form in favour of “Finance officer, University of Lucknow” payable at Lucknow, which is not refundable in any case.
11. Tender form will be deposited in the office of the Proctor University of Lucknow, Last date of tender form submission is 06.09.2019 upto 3:00 PM. The tender will be opened on the same day at 4:00 PM. in the office of The Proctor, University of Lucknow.
12. Authorized signatory has keep all the original documents at the time of opening of tender.
13. All disputes are subjects to Lucknow Jurisdiction.

I/We have read and understand the above conditions and agree to abide by them.

**Authorized Signatory & Seal of the Tenderer**

**University of Lucknow****Description of work: Development of Parking near UCO Bank Building.**

Format/ Check list of Technical Bid

S.No.	Description	Yes	No
1.	Name of the firm		
2.	Address  Contact No.		
3.	Attach : Firm registration/ Partnership Registration Company Certificate (Attached Photocopy)		
4.	G.S.T. Registration (Attach Photocopy)		
5.	Permanent Account Number. Issued by Income Tax Department. (Attached Photocopy)		
6.	Attach IT returns of last three years		
7.	Furnish Demand draft of Rs. 1180.00 in favour of Finance Officer, University of Lucknow towards cost of Tender form DD No.....dt..... Bank..... Branch.....		
8.	Furnish DD of Rs. 65000.00 in favour of Finance Officer, University of Lucknow towards EMD DD No.....dt..... Bank..... Branch.....		

Date:

**Signature of Authorized signatory  
Seal**

## Annexure – C

### Works Department, University of Lucknow

**Name of Work: Development of Parking near UCO Bank Building.**

#### Format of Financial Bid

**I/we here by tender rates for different items as given below.**

Sl. No.	Particulars of work	Qty.	Unit	Rate per Unit (Rs.)	Amount (Rupees)
1.	Dismantling of brick wall as per S.I. No. 692	76.00	m <sup>3</sup>		
2.	Earth work in excavation as per S.I. No. 252.	69.30	m <sup>3</sup>		
3.	Laying cement concrete as per S.I. No. 275.	17.33	m <sup>3</sup>		
4.	Brick work in wall as per S.I. No. 305(b).	171.47	m <sup>3</sup>		
5.	Plastering over wall as per S.I. No. 583	700.76	m <sup>2</sup>		
6.	Plastering over wall as per S.I. No. 584.	175.00	m <sup>2</sup>		
7.	Preparation of base with putty as per D.S.R. item No. 13.80	410.00	m <sup>2</sup>		
8.	Painting with weather coat as per DSR. Item No. 13.47.1	412.00	m <sup>2</sup>		
9.	Preparation and consolidation of subgrade as per DSR item no. 16.1 .	1260.00	m <sup>2</sup>		
10.	Supply and stacking of stone screening 11.20mm nominal size and laying spreading and compacting stone aggregate as per DSR item no. 16.37+16.40.	210.00	m <sup>3</sup>		
11.	Providing and laying 80mm thick zig-zag in interlocking tiles as per UPPWD rate. (Chapter 20)	1260.00	m <sup>2</sup>		
12.	Providing and laying non-pressure NP-3 class RRC pipe as per DSR item no. 19.35.5 (1200mm dia RCC pipe).	8.00	Mt.		
13.	Construction of brick masonry main hole as per DSR item No. 19.7.3.1 + 19.8.2.1 size 120x90cm x (2.90).	03	No.		
14.	Providing and laying non-pressure NP-3 class as per DSR item no. 19.35.2 600mm dia RCC Pipe.	23.50	Rmt.		
15.	Providing and laying cement concrete as per DSR Item No. 5.1.2.	34.800	m <sup>3</sup>		
16.	Mild steel work in plane as per S.I. No. 504.	36.50	Qtl.		
17.	Providing and laying drain water pipe of 110mm dia PVC pipe of 6.00 kg/cm <sup>2</sup> pressure.	66.00	Mt.		
18.	Providing and laying drain water pipe line as per required in depth having 75mm dia 6.00 kg/cm <sup>2</sup> pressure.	66.00	Rmt.		
19.	Fabrication of M.S. gate as per S.I. No. 503.	505.00	Kg		
20.	Dismantling of cement concrete dumped in culvert by LMRC. c. Mason d. Labour	08 20	No. No.		
21.	20mm plastering and finish with neat cement over concrete surface S.I. No. 597.	310.00	m <sup>2</sup>		
<b>Total</b>					
Good & Services Tax @.....					
<b>Grand Total</b>					

**Signature of tenderer with seal**